


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Hodgeman County. Sec. 23 Twp. 21 Rge. 26 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW SW
Lease Owner B & R Drilling, Inc.
Lease Name Sinclair Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 3, 1951 19
Application for plugging filed September 2, 1951 Verbally 19
Application for plugging approved September 2, 1951 " 19
Plugging commenced September 3, 1951 19
Plugging completed September 3, 1951 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 5040' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	198'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging Record

First plug at 180' Cemented with 15 sacks
Plug No. 2 at 35' With 1/2 sack hulls and 10 sacks cement.

SEP 12 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to B & R Drilling, Inc.
Address Russell, Kansas


STATE OF Kansas, COUNTY OF Russell, ss.
W. A. Michaelis, Jr. (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W. A. Michaelis, Jr.*
Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 11 th day of September 1951

Care Sumner
Notary Public.

My commission expires 6-17-54



B & R Drilling, Inc.
Sinclair No. 1

SW SW SW of Section 23-21-26W
Hodgeman County, Kansas

Total Depth: 5040'
Comm: 8-3-51
Comp: 9-3-51

Casing

Cement

8 5/8" Set @ 198'

135 sacks of Universal

Formation	Depth
Surface Hole	135
Shale-Shells	198
Shale	350
Shale-Sand	820
Shale-Redbed	1000
Redbed	1025
Anhydrite	1045
Shale-Redbed	1300
Sand	1340
Shale-Redbed-Shells	1670
Lime-Shale	1700
Shale-Shells	2270
Shale-Anhydrite	2435
Shle-Shells	2465
Lime-Shale	3465
Shale-Shells	3570
Shale-Lime	3625
Lime-Shale	3835
Lime	4065
Lime-Chert	4105
Lime	4296
Lime-Shale	4380
Lime	4405
Lime-shale	4445
Lime-Chert	4603
Lime	4635
Lime-Chert	4880
Lime-Chert-Shale	4917
Shale-Lime	4928
Lime-Chert	4996
Lime	5040'

STATE OF KANSAS)
)SS
RUSSELL COUNTY)

RECEIVED
STATE CORPORATION COMMISSION
SEP 12 1951
CONSERVATION DIVISION

I hereby certify that the above information is true
and correct to the best of my knowledge.

Violet Feller

Subscribed and sworn to before me this 10th day of September, 1951.

Clara L. ...

Notary Public

My commission expires: 6-17-54

PLUGGING
FILE SEC 23-21-26W
BOOK PAGE 127 LINE 33