



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

DEC 14 1964

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Bill Walker of Rains & Williamson Oil Co. has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Co.

Complete Address: 1425 Wichita Plaza, Wichita, Kansas

Lease Name: Carroll Well No. # 1

Location: C E/2 SE NW Sec. 20 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3630 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

297' of 8 5/8" surface pipe, cement circulated with 225 sacks.  
Fill hole with drilling mud to 290', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling  
mud to 40', 2nd cementing plug, bridge with hulls, and cement  
with 10 sacks to base cellar. Bridged and cement rat hole with  
2 sacks.

Very truly yours,

*Archie Elving*