

State of Kansas



FORM - CP-2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

FEB 21 1964
2-21-64
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Vaughn Francis of Terrel Drlg. & Producing has this
date requested permission to plug the following described well:

Mr. Francis guarantees payment of the plugging fee.

Operator's full Name: Fred B. & Philip F. Anschutz

Complete Address: 1521 Wichita Plaza, Wichita, Kansas

Lease Name: Trager Well No. # 1

Location: C SE SE Sec. 30 Twp. 30 Rge. 20 (E) (W) W

County Kiowa Total Depth 5202 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Francis was instructed to plug the well as follows:

321' of 8 5/8" surface pipe, cemented with 250 sacks. Fill
hole with mud to 300', 1st cementing plug, bridge with hulls,
and cement with 25 sacks. Fill hole with mud to 40', 2nd
cementing plug, bridge with hulls, and cement with 10 sacks.
Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent