

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUL 29 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Ralph Schuyler of Strata Drilling Co. has this
 date requested permission to plug the following described well:

Mr. Schuyler guarantees payment of the plugging fee.

Operator's full Name: Time Petroleum Co.

Complete Address: 815 Union National Bank Bldg., Wichita, Kan.

Lease Name: Stockwell Well No. # 1

Location: C SE NW Sec. 11 Twp. 30 Rge. 20 (E) (W) W

County Kiowa Total Depth 5334 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Schuyler was instructed to plug the well as follows:

320' of 8 5/8" surface pipe, cemented with 275 sacks. Fill
hole with mud to 240', 1st cementing plug, 1/4 sack hulls,
cement with 20 sacks. Fill hole with mud to 40', 2nd cement-
ing plug, 1/4 sack hulls, cement with 10 sacks to base cellar.
Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent