

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSIONJUL 13 1975
7-3-75
CONSERVATION DIVISION
WICHITA, KANSASJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Hanna of Anadarko Production has this
date requested permission to plug the following described well:Mr. Hanna guarantees payment of the plugging fee.Operator's full Name: Anadarko Production CoComplete Address: Box 351 Liberal, KSLease Name: Gillette A Well No. 7Location: NW/NW Sec. 15 Twp. 30S Rge. 19 (E)(W) WCounty: Kiowa Total Depth 5189 Oil Well Gas Well Input Well SWD Well D & A Lost Hole Mr. Hanna was instructed to plug the well as follows:422 ft 8 5/8 surface cemented with 450 sacks. 5189 ft 4 1/2long string cemented with 140 sacks. Top perf. 5094 ft.Pump 30 sacks cement to 4800 ft. Pulled 3770 ft 4 1/2.Pump/50 sacks cement to 450 ft. Mud to 40 ft, plug, 1/2sack hulls, 10 sacks cement to surface.Pumped by Hallibutyn Cementing Great Bend, KS
Very truly yours,