

State of Kansas



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 22 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

April 18, 1968.

Dear Sir:

Anadarko Prod. Co.

Mr. Paul Gatlin of ~~Garvey Drilling Co.~~ has this date requested permission to plug the following described well:

Mr. Gatlin guarantees payment of the plugging fee.

Operator's full Name: Anadarko Prod. Co.

Complete Address: Box 351 Liberal, Kansas.

Lease Name: Dean B Well No. #1

Location: C-NE-SE Sec. 4 Twp. 30S Rge. 10w (E) (W) W

County: Kiowa Total Depth 5230' 30S Oil Well

Gas Well Input Well SWD Well D & A y Lost Hole

Mr. Gatlin was instructed to plug the well as follows:

427' of 8 5/8" surface pipe circulated with 450 sacks
cement. 35 sacks cement spotted at 5150 ft. Mud to 400 ft.
plug. 1/2 sack hulls & 25 sacks cement. Mud to 30 ft. plug, 1
sack hulls & 12 sacks cement to surface. Rathole bridged &
2 sacks cement.

Very truly yours,

Herbert Justus
Conservation Division Agent