

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

19 December 1981

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-097-20,827

Dear Sir:

Mr. Glen Conway of Lawson Drilling Co., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Graham-Michaelis Co., Inc.

Complete Address: 211 N. Broadway Bldg 247 Wichita Kansas 67202

Lease Name: Robbins Morton Well No. 1-35

Location: C-SW-5W Sec. 35 Twp. 30 Rge. 18W (E) (W)

County: Kiowa Total Depth: 5125'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Conway was instructed to plug the well as follows:

There is 80' of 8 1/8" surface casing cement circulated with 800 sbp of cement. The anhydrite is at 1070'. 1st plug at 1000' with 50 sbp of cement. 2nd plug pushed rubber plug to 750' and put 35 sbp of cement on top of it. 3rd plug at 40' to 0' with 10 sbp of cement. Then pumped 5 sbp of cement in rat hole. The cement used was Common with 2% cell 3% cc. The plugging was accomplished by Dowell Cementing.

Very truly yours,

Paul Luth
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1981
CONSERVATION DIVISION
Wichita, Kansas

12-22-81