

State of Kansas



15-097-20023-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
JUN 26 1967  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill,  
filed June 9, 1967.

Dear Sir:

Mr. Don Rider of K & E Drilling, Inc. has this  
date requested permission to plug the following described well:

Mr. Rider guarantees payment of the plugging fee.

Operator's full Name: K & E Drilling, Inc.

Complete Address: 719 Union Center Bldg., Wichita, Kansas 67202

Lease Name: Kane Unit Well No. # 1-12

Location: C NW SE NW Sec. 12 Twp. 30 Rge. 18 (E) (W) W

County Kiowa Total Depth 4905' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Rider was instructed to plug the well as follows:

38' of 13 3/8" surface pipe, cemented with 47 sacks. 374' of 8 5/8"  
surface pipe, cement circulated with 253 sacks. Fill hole with drilling  
mud to 365', 1st cementing plug, bridge with 1/2 sack of hulls, and cement  
with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug,  
bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar.  
Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent