

State of Kansas



15.097.10209.00.00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
CONSERVATION DIVISION

JAN 27 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill,  
filed December 29, 1966

Dear Sir:

Mr. Don Rider of K & E Drilling, Inc. has this  
date requested permission to plug the following described well:

Mr. Rider guarantees payment of the plugging fee.

Operator's full Name: K & E Drilling, Inc.

Complete Address: 719 Union Center Bldg., Wichita, Kansas

Lease Name: Fincham Unit Well No. # 1

Location: C NE SW Sec. 2 Twp. 30 Rge. 18 (E)(W) W

County Kiowa Total Depth 5525' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Rider was instructed to plug the well as follows:

463' of 8 5/8" surface pipe, cement circulated with 300 sacks. Fill  
hole with drilling mud to 400', 1st cementing plug, bridge with 1/2 sack  
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',  
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Audie Elving  
Conservation Division Agent