

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

SEP 30 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts.
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Buck Unruh of Southwest Casing Pulling has this
 date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: Route 2, Great Bend, Kansas

Lease Name: Kane Well No. # 1

Location: C SE NW Sec. 17 Twp. 30 Rge. 17 (E) (W) W

County Kiowa Total Depth 4978 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Unruh was instructed to plug the well as follows:

215' of 10.3/4" surface pipe, cemented with 150 sacks.
4975' of 4 1/2" long string, cemented with 150 sacks. Plugg-
ed back to 4918'. Top perforation 4886'. Sand to 4870',
cement with 3 sacks. Fill hole with mud to 225', 10' rock
bridge, cement with 25 sacks. Fill hole with mud to 40',
10' rock bridge, cement with 15 sacks to base cellar.
 Very truly yours,

Archie Elving
 Conservation Division Agent