



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 3 1968

CONSERVATION DIVISION
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Ed Walker of Garvey Drilling Company has this
date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name: Runnymede Unit "D" Well No. # 1

Location: Approx. C SE Sec. 11 Twp. 30 Rge. 17 (E)(W) W

County Kiowa Total Depth 5001' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

524' of 8 5/8" surface pipe, cement circulated with 300 sacks.

Fill hole with drilling mud to, 300', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling mud
to 40', 2nd cementing plug, bridge with hulls, and cement with 10
sacks to base of cellar, Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent