


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Rice County. Sec. 4 Twp. 21 Rge. 6 (E) W (W)
Location as "NE/CNW&SW" or footage from lines SE SW NW
Lease Owner Sterling Drilling Company
Lease Name Cleavinger Well No. 4
Office Address Sterling, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 11-10-65 19
Plugging completed 11-11-65 19
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3471 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	160'	None
				5-1/2"	3434'	2966'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3470', pushed plug to 3410', sanded to 3400' and dumped 5 sacks of cement @ 3400' with dump bailer. Pulled 5 1/2" casing, set rock bridge from 160' to 150' and dumped 20 sacks of cement @ 150'. Mudded hole to 30', set rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

NOV 23 1965

PLUGGING COMPLETE.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner/contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of November, 19 65

Milton J. Volin
Notary Public.

My commission expires May 20, 1968

15.159.04365.0000

STERLING DRILLING COMPANY
Sterling, Kansas

WELL LOG ----- Cleavinger #4
LOCATED: SE/4 SW/4 NW/4 Section 4-21S-6W, Rice County, Kansas.

OWNER: Seeger Oil and Gas Company, et al
CONTRACTOR: Sterling Drilling Company

COMMENCED: May 25, 1950
COMPLETED: June 5, 1950 (w/r) June 19, 1950 (w/c.t.)

TOTAL DEPTH: 3438' (w/r)
3504' (w/c.t.)

LOG

0 - 70	Sand
70 - 160	Red Bed
160 - 760	Shale and Shells
760 - 1865	Shale and Lime
1865 - 2425	Shale
2425 - 2585	Lime
2585 - 2655	Lime and Shale
2655 - 2710	Lime
2710 - 2800	Shale
2800 - 2880	Lime and Shale
2880 - 3380	Lime
3380 - 3420	Lime and Shale
3420 - 3436	Conglomerate
3436 - 3438	Chat
3438 - 3446	Chat, Shale and Show of Oil
3446 - 3451	Brown Chat
3451 - 3463	Chat
3463 - 3475	Brown Chat
3475 - 3491	V. Color Chat, Hard and Sharp
3491 - 3497	V. Color Chat
3497 - 3501	Chat, Hard
(or 3504	Rotary Measurement)

CASING RECORD

160' of 8-5/8" surface pipe cemented with 125 sacks cement.

3434' 5 1/2" set @ w/ 35 sacks cement.

PRODUCTION

6-13-50 Plug back 3504 to 3471. Put 20 qts. Solidified.
6-18-50 Perforated with 24 shots from 3429 to 3437.

RECEIVED
STATE CORPORATION COMMISSION

OCT 18 1965

CONSERVATION DIVISION
Wichita, Kansas