

R


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rice County, Sec. 4 Twp. 21 S Rge. 6 (E) W (W)

Location as "NE/CNWSW" or footage from lines NW NW NE NWNENW

Lease Owner Plains Exploration Co.

Lease Name Alexander Well No. 2

Office Address Denver, Colo.

Character of Well (completed as Oil, Gas or Dry Hole) Injection

Date well completed January 19 52

Application for plugging filed July 6, 19 68

Application for plugging approved July 15, 19 68

Plugging commenced Oct. 14 19 68

Plugging completed Oct. 17 19 68

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well 3460 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1170'
Dumped 5 sacks of cement at ~~XXXXXX~~ Shot pipe off ~~at 1570'~~ and
Pulled pipe and mudded hole to 220'. Set rock bridge from
220' to 210' and dumped 60 sacks of cement. Mudded to 40' and
set rock bridge from 40' to 30'. Dumped 10 sacks of cement
at top of surface.

RECEIVED
STATE CORPORATION COMMISSION
OCT 29 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Bert Self
Address Hutchinson, Kans.

STATE OF Kans. COUNTY OF Reno, ss.
Employee (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self
R. D. #4, Hutchinson, Kans.
(Address)

Subscribed and sworn to before me this 22nd day of October 19 68



October 19, 1969 Notary Public.

STERLING DRILLING CO.

STERLING, KANSAS

WELL LOG ----- ALEXANDER #2

Location - NW/4 NE/4 NW/4 of Section 4-21-6, Rice County, Kansas

Owner - Plains Exploration Company
 Rotary Drilling Contractor - Sterling Drilling Company
 Cable Tools Contractor - Sterling Drilling Company

Commenced - 1-1-52
 Completed - 1-11-52 (w/r)
 - 1-18-52 (w/c.t.)

Total Depth - 3435' (w/r)
 - 3460' (w/c.t.)

ELEVATION: 1626 DF
 1624 Gr

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 15 1968
 CONSERVATION DIVISION
 Wichita, Kansas

LOG

0- 140	Sand, Clay and Shale
140- 150	Shale and Shells
150- 750	Shale, Shells and Salt
750- 900	Shale and Shells
900-2335	Lime and Shale
2335-2685	Lime
2685-2720	Shale
2720-2775	Sandy Shale
2775-3255	Lime
3255-3412	Lime and Shale
3412-3435	Chat

CASING RECORD

135' of 8-5/8" Surface Pipe
 Cemented at 135' with 100 Sacks Cement

3462' of 5 1/2" O. D. Casing
 Cemented at 3435' with 75 Sacks Cement

FORMATION TOPS

Lansing-Kansas City	2870'
Basal Pennsylvanian Congl.	3408'
Mississippian "Chat"	3410'

(All tops Kelly Bushing)

PRODUCTION: Producer

CABLE TOOLS RECORD: Moved in; cleaned out to rotary total depth, 3435'.
 Drilled deeper, to 3460'. Had a small show of oil 3440';
 good show of oil and gas 3451-57. Hole filled up 1500'
 in 15 hours. Put on the pump.