

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Rice County. Sec. 3 Twp. 21S Rge. 6W (XXXXXXXXXX)

Location as "NE/CNW%SW%" or footage from lines SW SW NE  
Lease Owner Phillips Petroleum Company  
Lease Name W. M. Miller Well No. 4  
Office Address Box 287, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed March, 1931 19\_\_\_\_  
Application for plugging filed Oct. 27, 1962 19\_\_\_\_  
Application for plugging approved October 30, 1962 19\_\_\_\_  
Plugging commenced 11-18-62 19\_\_\_\_  
Plugging completed 11-19-62 19\_\_\_\_  
Reason for abandonment of well or producing formation Unprofitable  
If a producing well is abandoned, date of last production June, 1956 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Gilbert Toman  
Producing formation Miss. Chat Depth to top 3366' Bottom \_\_\_\_\_ Total Depth of Well 3384' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION    | CONTENT | FROM | TO | SIZE     | PUT IN | PULLED OUT |
|--------------|---------|------|----|----------|--------|------------|
| Topeka       | Dry     | 2289 |    | 20"      | 60'    | None       |
| Heebner      | Dry     | 2590 |    | 7"       | 3094'  | 600'       |
| LKC          | Dry     | 2800 |    | 5 1/2"   | 3364'  | 3130'      |
| Conglomerate | Dry     | 3356 |    | 4" liner | 67'    | None       |
| Chat         | Oil     | 3368 |    |          |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with rock from 3384' to 3315'.

Dumped 5 sx cmt from 3315' to 3280'.

Spotted 30 sx cement plug 200 to 150'.

Mudded hole from 150' to 116', spotted 50 sx cement 116' to surface. Well plugged and abandoned 11:00 a.m. 11-19-62.

11-26-62

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 22 1962  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Knight Casing Pulling Unit  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
M. E. Michael Dist. Supt. (employee of owner) ~~or licensed operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M E Michael  
Box 287, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of November, 19 62

My commission expires 11-18-65  
Joseph M Beal Notary Public.

15.159.05246.0000

EXPLORATION RECORD

Lease W. M. Miller

Well 4

| Formation Name       | Top   | Base | Remarks |
|----------------------|-------|------|---------|
| Surface sand         | 0     | 30   |         |
| Clay and sand        | 30    | 65   |         |
| Red Bed              | 65    | 285  |         |
| Sand, shale & shells | 285   | 675  |         |
| Shale and salt       | 675   | 885  |         |
| Shale and lime       | 885   | 1260 |         |
| Lime                 | 1260  | 1645 |         |
| Lime and shale       | 1645  | 1900 |         |
| Shale                | 1900  | 2290 |         |
| Lime                 | 2290  | 2600 |         |
| Shale                | 2600  | 2815 |         |
| Lime                 | 2815  | 3125 |         |
| Shale and Lime       | 3125  | 3370 |         |
| Lime                 | 3370  | 3390 |         |
| Total Depth          |       | 3390 |         |
| Present Total Depth  |       | 3384 |         |
| Top Topeka           | 2289' |      |         |
| Heebner              | 2590' |      |         |
| LKC                  | 2800' |      |         |
| Congl.               | 3356' |      |         |
| Chat                 | 3368' |      |         |

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 26 1962  
 CONSERVATION DIVISION  
 Wichita, Kansas