


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Rice County, Sec. 3 Twp. 21S Rge. (E) 6 (W)
Location as "NE/CNW/SW" or footage from lines SW NE NW
Lease Owner Sterling Drilling Co.
Lease Name Miller "B" Well No. 3
Office Address Sterling, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 19
Application for plugging filed November 6, 1968
Application for plugging approved November 7, 1968
Plugging commenced November 25 19 68
Plugging completed November 30 19 68
Reason for abandonment of well or producing formation
Uneconomical to produce
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Tolman
Producing formation Mississippi Depth to top Bottom Total Depth of Well 3418 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi				10-3/4"	90'	none
				5-1/2"	3376	2636

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

5 1/2' @ 3376' w/40 sacks.
Sanded hole on top of bailer 3360'-3345'.
5 sacks cement @ 3345.
Shot pipe @ 3021, 2921, 2891, 2802, 2739, 2622' (6 shots).
Pulled 2635.65' (85 jts) 5 1/2' casing.
Mudded hole to 210'. Rock bridge 210'-200'.
50 sacks cement @ 200'.
Rock bridge 40'-30'.
15 sacks cement to surface.
Plugging complete.

RECEIVED
STATE CORPORATION COMMISSION
DEC 16 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Braden-Deem, Inc.
Address 210 One Twenty Bldg., Wichita, Kansas

STATE OF ~~Sedgwick~~ Kansas, COUNTY OF Sedgwick, ss.
Doy C. Deem (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *[Signature]*
210 One Twenty Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13 day of December, 1968

My commission expires March 21, 1970

[Signature] Notary Public.

WELL LOG ----- MEMBER #3

Location - SW NE NW Section 3-213-04, Rice County, Kansas.

Owner - Sterling Drilling Company, et al
Contractor - Sterling Drilling Company

Commenced - October 12, 1947
Completed - October 25, 1947 (w/r)
November 6, 1947 (cable tools)

Elevation 1594 D.F.

Total Depth - 3376 (w/r)
3419 (cable tools)

CASING RECORD

30' 10-inch Surface Pipe
Cemented with 120 sacks cement

3376' 5 1/2-inch Oil String
Cemented with 40 sacks

Log

0- 25	Sand
25-1135	Shale & Shells
1135-1260	Lime & Shale
1260-1325	Lime
1325-1365	Shale
1365-1620	Lime
1620-2500	Shale & Lime
2500-2620	Lime
2620-2745	Shale
2745-3325	Lime
3325-3370	Lime & Shale
3370-3376	Chert
3376-3419	Cable Tools

FORMATION SOCS

(Corrected to Derrick Floor)
Top Chert Cong. 3361 da - 17'
Miss. Chert 3372 da - 17'

PRODUCTION

Producers. Pay from 3415-3419

RECEIVED
STATE CORPORATION COMMISSION
NOV 7 1968
CONSERVATION DIVISION
Wichita, Kansas