

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rice County, Sec. 3 Twp. 21 Rge. 6 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE SW NW

Lease Owner Sterling Drilling Company

Lease Name Miller Well No. 4

Office Address Sterling, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19__

Application for plugging filed _____ 19__

Application for plugging approved _____ 19__


Plugging commenced 11-23-65 _____ 19__

Plugging completed 11-26-65 _____ 19__

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3430 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10"	107'	None
				5-1/2"	3376'	3179'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3430', sanded hole to 3360' and dumped 5 sacks of cement @ 3360' with dump bailer. Pulled 5 1/2" casing, bailed hole to 150', set rock bridge to 140' and dumped 30 sacks of cement @ 140'. Mudded hole to 20', set rock bridge and capped well with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

DEC - 7 1965

CONSERVATION DIVISION
WICHITA, KANSAS

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of December, 19 65

My commission expires May 20, 1968

Milton J. Volin
Notary Public.

T-33

WELL LOG

WELLER NO. 4

Location - NE SW NW Section 3-21S-6W, Rice County, Kansas.

Owner - Sterling Drilling Company, et al
Contractor - Sterling Drilling Company

Commenced - November 19, 1947

Completed - December 1, 1947 (w/r)
December 5, 1947 (cable tools)

T.D. 3397' (w/r)

Elevation 1591

RECEIVED
STATE CORPORATION COMMISSION
NOV 3 1965
CONSERVATION DIVISION
Wichita, Kansas

LOG

0- 30	Sand
30- 50	Sand & Shale
50- 95	Shale & Shells
95- 360	Shale & Red Bed
360- 445	Shale & Shells
445- 920	Shale & Salt
920-1145	Lime & Shale
1145-1180	Shale & Shells
1180-1295	Lime
1295-2090	Lime & Shale
2090-2300	Shale & Shells
2300-2500	Lime
2500-2730	Shale
2730-2810	Lime
2810-2905	Lime & Shale
2905-3305	Lime
3305-3370	Shale & Lime
3370-3378	Shale
3378-3396	Conglomerate
3396-3397	Chert - Miss.
3397-3450	Cable Tools

CASING RECORD107' 10-inch Casing
Cemented with 100 Sacks Cement3376' 5 1/2-inch Casing
Cemented with 40 Sacks CementTOPS (Corrected to Derrick Floor)Chert Conglomerate 3375 dm -1782
Miss. Chert 3395 dm -1802PRODUCTION

Producer. Pay from 3424-3450.