


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Rice County, Sec. 3 Twp. 21 Rge. 6 (E) (W)
Location as "NE/CNWSW" or footage from lines SE NW NW
Lease Owner Sterling Drilling Company
Lease Name Miller #5 Well No.
Office Address Sterling, Kansas 67579
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 3/8/72 19
Plugging completed 2/10/72 19
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation Depth to top Bottom Total Depth of Well 3428 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	105	none
				5 1/2"	3392'	3098'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3428', ran sand to 3360' and dumped 5 sacks of cement.
Loaded hole, shot pipe at 3093', pulled 99 joints of 5 1/2" casing.
Set rock bridge at 210 to 200' and dumped 50 sacks of cement. Mud to 40', set rock bridge and dumped 10 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
FEB 18 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Noel Knight*
CHASE, KANSAS (Address)

Subscribed and sworn to before me this 14th day of February, 1972
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My commission expires Feb. 15, 1975

day of February, 1972
Margaret Melcher
Notary Public.

T-34

Location - SE NW NW Section 3-21S-6W, Rice County, Kansas.

Owner - Sterling Drilling Company, et al
Contractor - Sterling Drilling Company

Commenced - December 8, 1947
Completed - December 18, 1947 (w/r)
December 28, 1947 (cable tools)

T.D. 3394' (w/r)

Elevation 1590 D.F.

LOG

0- 30	Surface Sand
30- 105	Red Bed & Shale
105- 900	Shale & Shells
900-1275	Shale & Lime
1275-1380	Shale & Shells
1380-1545	Bro. Lime
1545-1685	Shale & Lime
1685-2300	Shale & Shells
2300-2600	Lime
2600-2630	Lime & Shale
2630-2740	Shale
2740-3295	Lime
3295-3380	Shale
3380-3394	Cong.
3394-3423	Cable Tools

CASING RECORD

105' 8-inch Surface Pipe
Cemented with 100 Sacks Cement

3392' 5 $\frac{1}{2}$ -inch Casing
Cemented with 50 Sacks Cement

TOPS. (Corrected to Derrick Floor)

Top Chert Cong	3377 da	-1787
Top Weathered Yellow		
Miss. Material	3390 da	-1800
T.D. in Weathered		
Yellow Miss. Chert	3392	

PRODUCTION

Producer.

RECEIVED
STATE CORPORATION COMMISSION
FEB 18 1972
CONSERVATION DIVISION
Wichita, Kansas