


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rice County, Sec. 3 Twp. 21 Rge. 6 (E) (W)
Location as "NE/CN/WSW" or footage from lines. NE NW NW
Lease Owner Sterling Drilling Company
Lease Name Miller #8 Well No.
Office Address Sterling, Kansas 67579
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 2/1/72 19
Plugging completed 2/8/72 19
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation Depth to top Bottom Total Depth of Well 3428 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	128	none
				5 1/2"	3401	2625'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Poured 10 gallons diesel down 5 1/2" and worked bridge out. Ran sand to 3390', dumped 5 sacks of cement. Loaded hole, shot pipe at 2903', 2813', 2718', 2625', worked pipe loose and pulled 84 joints. Bailed fluid to 240', set 10' rock bridge and dumped 35 sacks of cement. Mud to 40' and set 10' rock bridge and dumped 10 sacks of cement.

PLUGGING COMPLETE.


RECEIVED
STATE CORPORATION COMMISSION
FEB 14 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 9th day of February, 1972



NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melale
Notary Public.

15.159.05245.0000

GROUP EXPLORATION CO.

BOX 218
STERLING, KANSAS

May 21, 1952

RECEIVED
STATE CORPORATION COMMISSION
JAN 14 1972
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG ----- MILLER #3

Location - NE/4 NW/4 NW/4 Section 3-21-6, Rice County, Kansas

Owner - Sterling Drilling Company et al
Rotary Drilling Contractor - Group Exploration Company
Cable Tools Contractor - Sterling Drilling Company

Commenced - 4-21-52
Completed - 5-1-52 (w/r)
 - 5-17-52 (w/c.t.)

Total Depth - 3401' (w/r)
 - 3423' (w/c.t.)

ELEVATION: 1592 DF
 1539 Or

LOG

0- 60	Sand
60- 635	Shale
635- 935	Shale and Shells
935-2230	Shale and Lime
2230-2315	Lime
2315-2410	Shale and Lime
2410-2670	Lime
2670-2985	Lime and Shale
2985-3375	Lime
3375-3385	Conglomerate
3385-3401	Mississippi Chat
3401-3411	Chat
3411-3413	White Chat (soft)
3413-3416	V. Color Chat (soft)
3416-3420	White and Brown Chat
3420-3425	Gray and Brown Chat (soft)
3425-3428	White Chat (soft)

CASING RECORD

123' of 3-5/8" Surface Pipe
Cemented with 75 Sacks Cement

3404' of 5 1/2" O. D. Casing set at 3401'
Cemented with 75 Sacks Cement

PRODUCTION: Producer

FORMATION TOPS:

Cherty Conglomerate 3377'
Mississippi 3385'