


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rice County, Sec. 3 Twp. 21 Rge. 6 (E) (W)
Location as "NE/CNW/SW" or footage from lines NW NW NW

Lease Owner Sterling Drilling Company

Lease Name Miller #6 Well No.

Office Address Sterling, Kansas 67579

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 9/20/71 19

Plugging completed 9/23/71 19

Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman

Producing formation Depth to top Bottom Total Depth of Well 3432 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	103	none
				5 1/2"	3382	2916'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3432', ran sand to 3370' and dumped 5 sacks of cement. Loaded hole, shot pipe at 3047', 2917', spotted 70 barrels of oil and displace it with 75 barrels water. Worked pipe loose and pulled 101 joints. Set 10' rock bridge at 210 to 200' and dumped 35 sacks of cement. Mudded to 40', set 10' rock bridge and dumped 10 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Noel J. Knight*
Chase, Kansas
(Address)

Subscribed and Sworn to before me this 27th day of September, 1971

MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

T-35

WELL LOG

MILLER "C" NO. 6

Location - Northwest Corner of Section 3-21E-6W, Rice County, Kansas

Owner - J. A. Davis, J. R. Child, H. E. Billman, Rollin Mead, et al
Contractor - Sterling Grilling CompanyCommenced - February 27, 1948
Completed - March 12, 1948 (w/r)
April 11, 1948 (c/t)Total Depth - 3382' (w/r)
3432' (c/t)

ELEVATION - 1596 D.F.

LOG

0- 30	Surface Clay
30- 65	Sand
65- 106	Red Bed
106- 520	Shale & Shells
520- 965	Shale & Linc.
965-1580	Linc
1580-1800	Shale & Linc
1800-2305	Shale
2305-2620	Linc
2620-2750	Shale
2750-2905	Linc
2905-2965	Soft Linc
2965-3330	Linc
3330-3375	O.C. Shale
3375-3382	Cong.
3382-3432	Cable Tools

CASING RECORD

103' 8-5/8" Surface Pipe
Cemented with 100 Sacks Cement

3382' 5 1/2-inch O.D. Casing
Cemented with 50 Sacks Cement

FORMATION TOPS (Corrected to derrick floor)

Top Chert Cong. 3371 da - 1775
Miss Chert Weatherd. 3379 da - 1783
T.D. 3380'

PRODUCTION

Producer.

RECEIVED
STATE CORPORATION COMMISSION
SEP 17 1971
CONSERVATION DIVISION
Wichita, Kansas