

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-159-22,137-0000

LEASE NAME Miller

WELL NUMBER 3

3063 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 3 TWP. 21 RGE. 6 (X) or (W)

COUNTY Rice

Date Well Completed 2-3-86

Plugging Commenced 2-3-86

Plugging Completed 2-3-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kansas Horizon Oil, Inc.

ADDRESS Route #1 Box 86 Windom, Kansas 67591

PHONE# (315) 489-6221 OPERATORS LICENSE NO. 6522

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Phil Worley
to be filed by

Is ACO-1 filed? operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3480'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 260' w/50 sacks 60/40 pozmix 4% gel thru drill pipe

Top Plug: @ 60' w/20 sacks cement & bridged plug

10 sacks cement in Rat Hole 5 sacks in water well

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Co. License No. 5864

Address Box 877 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Ervin Neighbors

(Employee of Operator) or ~~Operator~~

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ervin Neighbors

(Address) Box 877 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 17th day of February, 1986

Dorothy M. Dague
Notary Public

My Commission Expires: 4-29-86

RECEIVED
STATE CORPORATION COMMISSION

FEB 11 1986

Form CP-4
Revised 08-84

CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S WELL LOG

DATE COMMENCED: Janaury 29, 1986
 DATE COMPLETED: February 3, 1986

Kansas Horizon Oil, Inc.
 MILLER #3
 93'W of SE SE NW
 Sec. 3, T21S, R6W
 Rice County, Ks.

ELEVATION: 1595 K.B.

0 - 70' Surface Soil, Sand, Clay
 70 - 503' Red Bed, Shale, Shells
 503 - 2604' Shale, Lime,
 2604 - 2608' Shale
 2608 - 2625' Lime & Shale
 2625 - 2633' Lime
 2633 - 2800' Shale
 2800 - 2815' Lime & Shale
 2815 - 3200' Lime
 3200 - 3419' Shale, Lime, Chert, Sand
 3419 - 3480' Chert, Lime
 3480' RTD

FORMATION DATA

Heebner	2604'
Toronto	2625'
Douglas	2633'
Br. Lime	2800'
Lansing	2815'
Cherokee	3301'
Conglomerate	3372'
Mississippi	3419'
RTD	3480'

Surface Pipe: Set new
 10-3/4", 36# pipe @207'
 w/200 sacks 60/40 pozmix
 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF EARTON) ss

Irvin Neighbors of lawful age, does swear and state that the facts and
 statements herein are true and correct to the best of his knowledge.

Subscribed and sworn to before me this 7th day of February 1986.

My Comm. Expires:

4-29-86

Ervin Neighbors

Dorothy M. Dague
 Notary Public

RECEIVED
 STATE CORPORATE COMMISSION

FEB 11 1986

CONSERVATION DIVISION
 State of Kansas