

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Rice SEC. 3 TWP. 21 RGE. 6 E/W
Location as in quarters or footage from lines:
200' N of SE NW NW

Lease Owner Sher-Ion Corporation
Lease Name Miller Well No. 1-A
Office Address 320 S. Broadway Sterling, KS 67579
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed 1-22-84
Application for plugging filed 1-22-84
Plugging commenced 1-22-84
Plugging completed 1-22-84
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Bittle
Producing formation _____ Depth to top _____ bottom _____ T.D. 3260'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Bottom Plug: @ 300' w/ 50 sacks 50/50 pozmix, 2% gel thru drill pipe
Top Plug: @ 40' w/Bridged Plug
10 sacks cement in Rat Hole
10 sacks cement in Water Well

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lobo Drilling Co.

STATE OF Kansas COUNTY OF Barton, ss.
Ervin Neighbors (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Ervin Neighbors
Box 877 Great Bend, KS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 27 day of January, 1984

Dorothy M. Dwyer
Notary Public.

My Commission expires: 4-29-86

RECEIVED
STATE CORPORATION COMMISSION

JAN 30 1984

DRILLER'S WELL LOG

DATE COMMENCED: January 18, 1984
DATE COMPLETED: January 22, 1984

Sher-Ion Corporation
MILLER A-1
200' N of SE NW NW
Sec. 3, T21S, R6W
Rice County, Ks.

ELEVATION: 1592 K.B.

FORMATION DATA

0 - 2598' Surface Soil, Sand, Clay
Shale, Lime
2598 - 2602' Shale
2602 - 2617' Lime & Shale
2617 - 3260' Lime
3260' RTD

Heebner 2598'
Toronto 2617'
Lansing 2800'
Stark 3093'
Swape 3109'
Spohn 3170'
RTD 3260'

Surface Pipe: Set new
8-5/8" pipe 20# Q224'
w/125 sacks 60/40 pozzolix
and 50 sacks common 28 gel
38 cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF CARTER

Ervin Neighbors of lawful age, does swear and state that the facts and
statements herein are true and correct to the best of his knowledge.

Ervin Neighbors

Subscribed and sworn to before me this 27 day of January 1984.

My Comm. Expires:

4-25-85

Marvin M. Hogue
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

JAN 30 1984

CONSERVATION DIVISION
Wichita, Kansas