

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Smokey Valley Resources

ADDRESS 1325 Hwy 56 Lyons, KS 67554

PHONE (316) 257-5529 OPERATORS LICENSE NO. 32081

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filled? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4202'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				14 3/4"	257'	none
				7"	3888'	720'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging was used, state the character of same and depth placed, from _____ feet to _____ feet each section. Sanded off bottom to 3250' & dumped 7 sks cement. Shot csg at 2000', 1800', 1200', 930'. Still wasn't loose. Pumped 45 sks cement to 900'. Set on plug for 2 hrs. Shot at 720', pipe came loose. Pulled up to 550' & pumped 45 sks cement. Pulled up to 310' & cc to surface w/160 sks. Pulled out rest of casing. Plugging complete. 60/40 4% gel.

7-30-97

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Smokey Valley Resources

STATE OF Kansas COUNTY OF Rice

Mike Kelso (Employee of Operator) or (Operator)


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 27th day of June, 19 97

My Commission Expires: 12/31/97



Notary Public