


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plot

Rice County, Sec. 3 Twp. 21 Rge. 6 (E) (W)  
Location as "NE/CNW/SE/SW" or footage from lines SW SE NW  
Lease Owner Sterling Drilling Company  
Lease Name Miller #1 Well No.  
Office Address Sterling, Kansas 67579  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 3/3/72 19  
Plugging completed 3/9/72 19  
Reason for abandonment of well or producing formation depleted.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman  
Producing formation Depth to top Bottom Total Depth of Well 3420 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	107	none
				5 1/2"	3400	2418'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Ran sand to 3390' and dumped 5 sacks of cement. Shot pipe at 3100', worked tension to 22". Ran shot in, stopped at 2425', shot pipe at 2425', pulled 77 joints. Bailed Fluid to 210', set rock bridge at 210' to 200' and dumped 45 sackk of cement. Mud to 40', set rock bridge and dumped 10 sacks of cement.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.  
NOEL J. KNIGHT

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Noel Knight*  
CHASE, KANSAS  
(Address)

Subscribed and sworn to before me this 10th day of March, 19 72

MARGARET MELCHER  
NOTARY PUBLIC  
Rice County, Kansas  
My Commission Expires  
Feb. 15, 1975

*Margaret Melcher*  
Notary Public.

Location - SW SE NW Section 3-213-6W, Rice County, Kansas

Owner - Sterling Drilling Company, et al  
Contractor - Sterling Drilling Company

Commenced - August 14, 1947

Completed - August 29, 1947

Total Depth 3420'

Elevation 1589

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 14 1972  
CONSERVATION DIVISION  
Wichita, KansasCasing Record107' 8-5/8" Surface Pipe  
Cemented with 65 Sacks Cement3400' 5 1/2" Casing  
Cemented with 40 Sacks CementProduction

50 Barrel.

1 1/2 Barrels oil per hour top Chatt.

3418 - Hole filled with oil in  
six hours.LOG

0- 40	Sand
40- 80	Sand & Clay
80- 160	Shale & Shells
160- 925	Shale Lime & Salt
925-1825	Shale & Lime
1825-2170	Shale
2170-2304	Shale & Shells
2304-2325	Lime
2325-2380	Shale
2380-2665	Lime
2665-2758	Shale
2758-2770	Lime
2770-2840	Shale & Lime
2840-3245	Lime
3245-3325	Shale & Lime
3325-3400	Conglomerate
3400-3402	Chatt
3402-3420	Cable Tools -

TD - 3420'

I hereby certify that the above is a true and correct copy of Driller's Log of well drilled in the SW SE NW Section 3-213-SW, Rice County, Kansas

STERLING DRILLING COMPANY

By \_\_\_\_\_  
President

Subscribed and sworn to before me this 8th day of September, 1947.

\_\_\_\_\_  
Notary Public

My term expires September 17, 1949.