

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation CommissionP. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Locate well correctly on above
Section Plat

Rice County, Sec. 3 Twp. 21 Rge. 6 W (E) (W)
 Location as "NE/CNW/SW" or footage from lines SE c SW
 Lease Owner Northridge Oil Co.
 Lease Name Rainey Well No. 3
 Office Address P.O. Box 18271 Denver, Colorado 80218
 Character of Well (completed as Oil, Gas or Dry Hole) oil
 Date well completed IO-23 19 35
 Application for plugging filed II-2 19 72
 Application for plugging approved II-2 19 72
 Plugging commenced II-2 19 72
 Plugging completed II-8 19 72
 Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
 Producing formation Depth to top Bottom Total Depth of Well 3419' Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5"		2,877'
				7"		1,088'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3419' to 3375'. Dumped 5 sx of cement. Pumped 30 sx of Gel through 7" casing at 300'. 100' of 7" casing was pulled. Pumped 175 sx of cement, with 4% Gel circulating cement. Pumped pressure 100#.

RECEIVED
STATE CORPORATION COMMISSION

NOV 10 1972

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Art Lamb Casing Pulling Co.
 Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas COUNTY OF Reno ss.
 Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb
 2809 King St. Hutchinson, Kansas 67501
 (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of November, 19 72

My commission expires January 5, 1974

Notary Public.

T-251

STENCILED

15.159.05244.0000

ORIGINAL

MAR 7 1936

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
Union National Bk Bldg, Wichita, Kansas.,

ROGERS ET AL.
Rainey No. 3.

Soc. 3 T. 21 R. 20
Sec. 30

Total Depth 3419
Comm. 12-5-34 Comp. 10-23-35.
Shot or treated.
Contractor.
Issued. 3-7-36.

County. Rice.

ASING.

15 1/2"	168'	8 1/2"	2830'
12 1/2"	146'	65/8"	3139'
10"	1846'		OK 1935

Elevation.

Production. Pot. 37B.

Figures Indicate Bottom of Formations.

Top Kansas City lime	2840
HFV 2875-80	
show oil and gas	3338
Top chat	3335
Total Depth	3419
3200' fluid.	

NOTE- The operator reports they did not keep a complete log of this well. If any of the companies have more information than is given here, please send it to the Bureau.

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1972
CONSERVATION DIVISION
Wichita, Kansas