

KANSAS

X

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 3 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Commercial Oil Company

Complete Address 5252 N. Broadway, Wichita, Kansas 67219

Lease Name Rainey Well No. 3

Location NW SE SE Sec. 3 Twp. 21 Rge. 6 (E) (W) X

County Rice Total Depth 3393'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Art Lamb Casing Pulling Co. and Haliburton Company

Address 2809 King, Hutchinson, Kansas License No. 440

Operation Completed: Hour 11 AM Day 29 Month July Year 1970

The above well was plugged as follows:

Hole filled with sand to 3350' and cemented with 5 sacks cement.

5 1/2" & 7" casing stuck together--decided not to pull)

Rock bridge set from 250' to 235' and 2 sacks cement dumped on bridge. 7" and 5 1/2"

casing shot at 200' and circulated with 250 sacks Poz-mix cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. B. Roman*
Well Plugging Supervisor

DATE 8/3/70
INV. NO. 2321-W