



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor  
MARION BEATTY Chairman  
HARRY G. WILES Commissioner  
RICHARD C. BYRD Commissioner  
RAYMOND B. HARVEY Secretary  
CLYDE E. MILLIGAN Counsel

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 1 1959  
CONSERVATION DIVISION  
Wichita, Kansas

Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

I have this date May 14, 1959, authorized the following plugging operation:

Operator's Full Name: Brunson-Spines, Inc.

Complete Address: 302 Union Center, Wichita, Kansas

Lease Name: Enns Well No. 1

Location: SE-NE-NW Sec. 31 Twp. 21 Rge. 3 (E) (W) X

County: McPherson Total Depth: 3826

Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other well as hereafter indicated: \_\_\_\_\_

Operator was instructed to plug well as follows:

Gun pits and circulate heavy mud. Fill hole to 300' with heavy mud.

Push plug and 1/4 sacks hulls to 300' and cement with 20 sacks.

Fill hole to 40' with heavy mud. Set solid bridge and cement with

10 sacks. Fill, Bridge, and cement rathole with 2 sacks.

Very truly yours,

Signed: *William J. Tomer*  
Conservation Division Agent