



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name H.L. Herbel

Complete Address: Box 327 Chase, Kansas 67524

Lease Name L.J. Driver Well No. # 1

Location C SW NW Sec. 25 Twp. 21 Rge. 8 (E) / (W)

County Rice Total Depth 3460'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Plugging Contractor: Pipe Pullers Inc.

Address: Ellinwood, Kansas License No. 462

Operation Completed: Hour 4 PM Day 12 Month 9 Year 68

The Above well was plugged as follows:

8 5/8"-258'-Circulated w/cement. 5 1/2"-3460'-Cemented. Top Perf.-3382'.

Sand hole to 3370'. 5 Sax.cement 3370' to 3340'. Mud 3340' to 250'.

Bridge 250' to 240'. 25 Sax.cement 240' to 165'. Mud 165' to 40'.

Bridge 40' to 30'. 10 Sax.cement 30' to 0. Pulled 2068'-5 1/2"-pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/16/68
INV. NO. 8464-11

Signed: [Signature]
Well Plugging Supervisor