

15.159.06637.0000

Form CP-3  
Rev. 6-26-62

KANSAS

*AL*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 11 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name H.L.Herbel

Complete Address: Box 327 Chase, Kansas 67524

Lease Name L.J.Driver Well No. # 2

Location C NW NW Sec. 25 Twp. 21 Rge. 8 (E) (W)

County Rice Total Depth 3475'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Pipe Pullers, Inc.

Address: Ellinwood, Kansas License No. # 462

Operation Completed: Hour 1 PM Day 9 Month 9 Year 68

The Above well was plugged as follows:

8 5/8"-258'-Circulated w/cement. 5 1/2"-3474'-Cemented. Top Perf. 3367'.  
Sand hole to 3350'. 5 Sax.cement 3350' to 3300'. Mud 3300' to 250'.  
Bridge 250' to 240'. 25 Sax.cement 240' to 165'. Mud 165' to 40'.  
Bridge 40' to 30'. 10 Sax.cement 30' to 0. Pulled 2821'-5 1/2"-pipe.

I hereby certify that the above well was plugged as herein stated

INVOICED  
DATE 9/11/68  
INV. NO. 8437-W

Signed: *[Signature]*  
Well Plugging Supervisor