

15.159.06639.0000

Form CP-3
Rev. 6-26-62



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name H. L. Herbel

Complete Address: P.O. Box 327, Chase, Kansas 67524

Lease Name Swartz Estate Well No. 1

Location SW NE NE SW Sec. 25 Twp. 21 Rge. 8 (E) (W) X

County Rice Total Depth 3475'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Plugging Contractor: Pipe Pullers, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 5 PM Day 6 Month December Year 1968

The Above well was plugged as follows:

Hole filled with sand to 3350' and cemented with 5 sacks cement.

Hole filled with mud to 260'. Rock bridge set from 260' to 250' and hole cemented

with 25 sacks cement. Hole filled with mud to 40'. Rock bridge set from 40' to 30'

and hole cemented to base of cellar with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 12/10/68
INV. NO. 8992-4

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1968
CONSERVATION DIVISION
Wichita, Kansas

Signed: Arthur J. Lorenz
Well Plugging Supervisor