

KANSAS  
STATE CORPORATION COMMISSION

15-009-16144-0000

CONSERVATION DIVISION AGENT'S REPORT

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Barton

Location: SE NE NE Sec. 8 Twp. 16 Rge. 13W (E) \_\_\_\_\_ (W) \_\_\_\_\_

Name of Field: \_\_\_\_\_ Total Depth: 3295

I have this date completed supervision of plugging of:

Lease Name: \_\_\_\_\_ Bitter \_\_\_\_\_ Well No. 1

Operator's Full Name: J. L. Chew

Complete Address: Box 526, Lyons, Kansas

Plugging Contractor Knight Casing Pulling Co.

Address: Box 304, Chase, Kansas License No. 436

Oil Well ☒ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No ☒

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 5:00 PM Day 1 Month 3 Year 1962

The above well was plugged as follows:

8 5/8" 270' cwc.

Sanded hole back to 3220' & dumped 4 sax cement with dump bailer.

Pulled pipe to 500'. Displaced 20 sax cement thru pipe. Pulled pipe

to 300' & displaced 20 sax cement thru pipe, with mud pump. Pulled

remainder of pipe. Mudded hole to 40', set rock bridge, & displaced

10 sax cement, cementing to base of cellar.

Signed: Don Truman  
Conservation Division Agent

Reviewed: Harold Willis  
Field Supervisor

Remarks:

RECEIVED INVOICED  
STATE CORPORATION COMMISSION  
DATE 3/16/62  
MAR 7 1962 INV. NO. 4648-u  
CONSERVATION DIVISION  
WICHITA, KANSAS

3-7-1962