

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 9 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Raymond Oil Company, Inc.

Complete Address 200 W. Douglas, Wichita, Kansas 67202

Lease Name Johnson Well No. 1

Location SE SE SW Sec. 10 Twp. 21 Rge. 7 (E) (W) X

County Rice Total Depth 3381'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Knight Casing Pulling Co., Inc. and Halliburton Co.

Address P.O. Box 405, Chase, Kansas License No. 624'

Operation Completed: Hour 9 AM Day 4 Month January Year 1973

The above well was plugged as follows:

Hole filled with sand to 3350' and cemented with 8 sacks cement.  
25 sacks gel-mud pumped through 8-5/8" casing at 300'. 200 sacks 50-50 Poz-mix  
cement with 2% gel added (total 4% gel) pumped through 8-5/8" casing at 200' and  
cement circulated to base of cellar. Mud and cement were pumped 1/2/73. Due to  
snow and icy roads, top of cement was not checked until 1/4/73. Top of cement  
7' below base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 1/9/73  
INV. NO. 6835-U