

DISTRICT CONSERVATION AGENT'S REPORT

[Handwritten signature]

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 61-39

LOCATION 11W-11W-SE

SEC. 20 TWP. 21 RGE. 12-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Tiepormann

Operator Musgrave Petro. Corp. Address 407 K. F. H. Bldg. Wichita-Kans.

Field _____ County Stafford

Total Depth 3601 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe - 8 1/2" - 300 ft. Circulated with cement.
5/8" casing set at 3570 ft. - no sacks of cement. Plugged
back to 3460 ft with sand & shot. Mounded 6 sacks cement at 3560 ft
Shot off & pulled the 5/8" casing - mud to 300 ft. Set back
bridge & 15 sacks of cement at 300 ft. mud to 35 ft - Bridge
& 10 sacks of cement at the surface.

Newman Casing Pulling Co. - Plugging Contractor

STATE CORPORATION COMMISSION

SEP 10 1951

CONSERVATION DIVISION

Wichita, Kansas

District Conservation Agent

Date 9-6-51

20 21 18W
61 59