

14
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 24 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Circle Oil Company, Inc.

Complete Address: 500 Bitting Bldg., Wichita, Kansas

Lease Name Tieperman Well No. # 3

Location SW NE SE Sec. 20 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3640'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Sage Drilling Company

Address: 500 Bitting Bldg., Wichita, Kansas License No.

Operation Completed: Hour 9:30AM Day 22nd Month Sept. Year 1965

The Above well was plugged as follows:

273' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fluid
level in the hole was at 95'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 250', and cemented with 25 sacks, through the
drill pipe. Fluid in the hole was now at 39'. 2nd cementing plug,
bridged solid with dry cement and hulls on fluid at 39', and cemented
with 10 sacks to the base of the cellar. Rat hole bridged and cemented
with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 9/27/65

INV. NO. 1853-W