

15.185.19553.0000

R

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

DEC 14 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Rains & Williamson Oil Company 12-14-1964

Complete Address: 1425 Wichita Plaza, Wichita, Kansas

Lease Name Carroll Well No. # 1

Location C E/2 SE NW Sec. 20 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3630

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Rains & Williamson Oil Company

Address: 1425 Wichita Plaza, Wichita, Kansas License No. _____

Operation Completed: Hour 9:45AM Day 11th Month Dec. Year 1964

The Above well was plugged as follows:

297' of 8 5/8" of surface pipe, cemented with 225 sacks. Fluid level
in the hole was at 80'. 1st cementing plug and 1/4 sack of hulls was
pushed in fluid to 290', and cemented with 25 sacks, through the drill
pipe. Hole was filled with drilling mud to 40', 2nd cementing plug,
bridged with hulls, and cemented with 10 sacks to the base of the cel-
lar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12-15-64

INV. NO. 344-W