

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Clinton Oil Co.

Complete Address 217 N Water Wichita, Ks

Lease Name F Syms Well No. 2

Location C NE/NW/NE Sec. 20 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3686

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 3:00 PM Day 14 Month 8 Year 1972

The above well was plugged as follows:

662 ft 8 5/8 surface pipe circulated. 3685 ft 5 1/2 long string cemented
with 125 sacks. Top perf. 3546 ft. Sand to 3525 ft. 5 sacks cement
with bailer. Pulled 2500 ft 5 1/2. Set 10 ft rock bridge at 300 ft.
Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed [Signature]
Well Plugging Supervisor

DATE 8-18-72

INV. NO. 617A-W