

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Stafford County, Sec. 36 Twp. 21 Rge. 12 (X) (W)

Location as "NE/CNW/SW" or footage from lines App. NE SE NW

Lease Owner John T. Hannah

Lease Name Mellies Well No. 1

Office Address Box 111 - Mission, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 5, 19 56

Application for plugging filed October 5, 19 56

Application for plugging approved October 5, 19 56

Plugging commenced October 5, 19 56

Plugging completed October 5, 19 56

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3626' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	284'	8 5/8"	284'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

From 3626' back to 210', heavy rotary mud. One plug set at 210' with 20 sacks cement. Heavy rotary mud back to 35'. Second plug set with 10 sacks of cement.

*10-11-56*

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Buick Drilling Inc.

Address P. O. Box 331, St. John, Kansas

STATE OF Kansas COUNTY OF Stafford, ss. H. R. Buick (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *H. R. Buick*

P. O. Box 331 - St. John, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of October, 19 56

*Robert A. Hoagness*  
Notary Public.

My commission expires December 26, 1959

PLUGGING  
FILE SEC. 36 T. 21 R. 12W  
BOOK PAGE 105 LINE 31

15.185.11578.0000

DRILLERS LOG

Mellies #1	Approx. NE SE NW, Sec. 36-21-12
Commenced R.D.: 9-24-56	Stafford County, Kansas
Completed R.D.: 10-5-56	Elevation: 1799 D.F.
Total Depth: 3626'	Initial Prod.: None
Casing Record: 284', 8 5/8"	Contractor: Buick Drilling Inc.

STRATA	DEPTH
Surface clay and sand	0 - 140
Red Bed and clay	140 - 284
Red Bed and sand	284 - 575
Anhydrite	575 - 590
Shale and shells	590 - 1585
Shale and lime	1585 - 2990
Lime	2990 - 3072
Lime and shale	3072 - 3144
Lime	3144 - 3333
Lime and shale	3333 - 3415
Lime	3415 - 3626 T.D.

I hereby certify the above a true and correct drilling log as reflected by the drilling reports of the Buick Drilling Inc.

BUICK DRILLING INC.

*H. R. Buick*  
 H. R. Buick, President

Signed and sworn to in my presence this 8th day of October, 1956, by H. R. Buick, President of the Buick Drilling Inc.

*Robert A. Shogren*  
 Notary Public

My commission expires December 26, 1959.

PLUGGING  
 FILE: SEC. 36 T. 21 R. 12W  
 BOOK PAGE 105 LINE 31

RECEIVED  
 NOTARY COMMISSION  
 OCT 11 1956  
 NOTARY DIVISION  
 Kansas