

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185-01480-0000

LEASE NAME Mueller I #1

WELL NUMBER \_\_\_\_\_

SPOT LOCATION SE SE

SEC. 29 TWP. 21 SRGE. 12W(E) of (W)

COUNTY Stafford

Date Well Completed \_\_\_\_\_

Plugging Commenced 9/12/84

Plugging Completed 9/17/84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Southern States Oil Co.

ADDRESS P.O. Box 1365, Great Bend, Ks. 67530

PHONE # (316) 792-2585 OPERATORS LICENSE NO. 5354

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3606'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				12"	248'	none
				5 1/2"	3596'	400'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3546' & 5 sacks cement. Shot pipe at 1200', 500', 400'. Pulled 16 joints of pipe. Plugged well with 2 hulls, 10 gel, & 150 sacks 60/40 poz 2% gel.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

RECEIVED  
STATE CORPORATION COMMISSION


SEP 24 1984

CONSERVATION DIVISION  
Wichita, Kansas

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524



My Commission expires: \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 21 day of Sept., 1984  
Irene Hoover  
Notary Public

WELL LOG BUREAU OF THE GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.


COPY

TORREY AND FEASTER.  
Mueller No. 1.

SEC. 29 T. 21 R. 12W.  
SEo SE

Total Depth. 3606  
Comm. 1-27-38 Comp. 2-20-38  
Shot or Treated.  
Contractor.  
Issued. 4-23-38

County Stafford.



Elevation.

CASING.

12" 248' 5" 3598'

Production. Pot. 1210 B.

Figures Indicate Bottom of Formations.

sand	215	K.C. lime	3337
red beds	257	lime	3430
red rock	685	cored from 3350 to 3 355	
shale	895	Run steel line at 3390	
shale and lime		no correction.	
shells	1029	limo and shalo	3480
shale and shells	1140	Viola lime and	
salt	1184	conglomerate	3528-36
salt and shale	1380	Viola limo	3536
shale and shells		Simpson Series	3546
and salt	1444	Simpson	3590
shale and lime		shalo green	3592
shells	1470	2 ft correction.	
lime and shale	1496	Siliceous limo	3600
lime	1670	Fine showing.	
lime and shale	1724	siliceous limo	3606 ←
lime	1743	Total Depth.	
lime and shale	1895		
hd sdy lime	1906		
lime and shale	2320		
shale	2396		
shale	2593		
shale and lime			
shells	2700		
limo and shale	2758		
shalo and lime			
shells	2790		
lime and shale	2867		
lime Topeka	2960		
lime brown	3023		
lime	3026		
broken lime	3051		
limo	3134		
limo hard	3160		
lime & shale	3173		
shalo and lime			
shells	3276		
lime K.C.	3301		
Top K.C. limo	3276 - 82		
broken lime	3305		
limo	3310		

RECEIVED  
STATE CORPORATION COMMISSION

AUG 30 1934

CONSERVATION DIVISION  
Wichita, Kansas