

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER: 15.185.12630.0000

LEASE NAME Mueller

WELL NUMBER A-3

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

_____ Ft. from S Section Line

_____ Ft. from E Section Line
 CN/2 NW SE

SEC. 29 TWP. 21S RGE. 12WE or (W)

COUNTY Stafford

LEASE OPERATOR Lasmo Energy Corporation

ADDRESS P.O. Box 1365
Great Bend, Kansas 67530

PHONE # (316) 792-2585 OPERATORS LICENSE NO. 4678

Date Well Completed _____

Character of Well Oil

Plugging Commenced 9-28-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-23-87

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? _____ Dist. # 1 Dodge City, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3578'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	290'	none
				5-1/2"	3577'	1560'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3250' and 5 sacks cement. Shot pipe @1800', 1560', pulled a total of 49 joints of 5-1/2" casing. Plugged surface with 2 hulls, 10 gel, 50 cement, 10 gel, 1 hull, plug and 125 cement, 60/40 pos, 6% gel.

Plugging Complete
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 27th day of October, 19 87

Irene Hoover
 Notary Public
 STATE CORPORATION COMMISSION

My Commission Expires: _____



OCT 29 1987 Form CP-4
 Revised 07-86

CONSERVATION DIVISION
 Wichita, Kansas

Well: Mueller "A" No. 3
 Location: C N/2 NW SE Section 29-21S-12W, Stafford County, Kansas
 Company: Virginia Drilling Company Inc. and Isern Bros.
 Contractor: Virginia Drilling Company, Inc.
 Commenced: March 23, 1947
 Completed: June 23, 1947
 Total Depth: 3578 1/2
 Elevation: 1860

FORMATION	DEPTH	TOPS	
Sand	0- 240	Lansing KC	3255
Shells-shale	240- 290	Viola Chert	3487
Shale	290- 660	Simpson	3523
Anhydrite	660- 690	Arbuckle	3577
Shale-shells	690-1120		
Salt-Shale	1120-1210	Circulate 1 hr @ 3578	
Salt-shells	1210-1420		
Shale-lime	1420-1645	8-5/8" csg. set @ 290	
Lime	1645-1720	5 1/2" csg. set @ 3577 1/2	
Lime-Shale	1720-1800		
Sandy lime	1800-1910		
Shale-lime	1910-2385		
Lime-shale-broken	2385-2495		
Lime-shale	2495-2580		
Lime	2580-2700		
Lime-broken	2700-2740		
Lime-shale	2740-2800		
Shale	2800-2840		
Lime	2840-3070		
Lime-shale	3070-3170		
Shale	3170-3225		
Shale-cherty-	3225-3242		
Lime-brown	3242-3252		
Lime-light	3252-3275		
Lime	3275-3405		
Lime-shale	3405-3494		
Lime-rough	3494-3510		
Cherty Conglomerate	3510-3520		
Shale	3520-3540		
Simpson	3540-3577		
Arbuckle	3577-3578 1/2		

3577
 1860
 -1717

Now comes S. A. Murphy, who states that he is familiar with the drilling of oil and gas wells and known of his own knowledge that the Mueller "A" No. 3 located in the C N/2 NW SE Section 29-21S-12W, Stafford County, Kansas, was drilled to a total depth of 3578 feet. Oil being found in the Siliceous Lime.

S. A. Murphy

Subscribed and sworn to before me, a Notary Public, this 21st day of July 1947.

Martha E. ...
 Notary Public

My Commission expires: February 5, 1949.

RECEIVED
 STATE CORPORATION COMMISSION

JUL 1 1947

CONSERVATION DIVISION
 Wichita, Kansas