

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 COLORADO DERRY BUILDING
 WICHITA, KANSAS 67202

WELL PLUGGING RECORD

TYPE OR PRINT
 PLEASE FILL OUT COMPLETELY
 AND MAKE REQUIRED AFFIDAVIT.

API NUMBER _____

LEASE NAME I. Mueller #2

WELL NUMBER _____

SPOT LOCATION CS/2 SW SE

SEC. 29 TWP. 21S RGE. 12W (E) OR (W)

COUNTY Stafford

DATE WELL COMPLETED _____

PLUGGING COMMENCED 9-15-83

PLUGGING COMPLETED 9-21-83

LEASE OPERATOR Southern States Oil Company

ADDRESS P.O. Box 1365 Great Bend, Ks. 67530

PHONE #() _____ OPERATORS LICENSE NO. _____

CHARACTER OF WELL
 (OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dodge City

IS ACG-1 FILED? _____ IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM _____ T.D. 3590'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS 1 CASING RECORD _____

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	315'	none
				5-1/2"	3584'	351'

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Plugged off bottom with sand to 3530' and set 5 sacks cement. Shot casing @2900', worked pipe and pipe parted 12 joints down. Pulled a total of 351'. Plugged well with 2 hulls, 10 gel, 50 cement, released plug and displaced with 100 sacks cement. Plugging Complete.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE No. 6050
 ADDRESS Box 347 Chase, Kansas 67524


STATE OF Kansas COUNTY OF Rice, SS.

R. Darrell Kelso (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) R. Darrell Kelso
 (ADDRESS) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO BEFORE ME THIS 23rd DAY OF September, 19 83

Irene Hoover
 NOTARY PUBLIC



MY COMMISSION EXPIRES: _____

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 26 1983
 CONSERVATION DIVISION
 Wichita, Kansas
 FORM CP-4
 REVISED 06-83

Owner: Isern Bros. & Anderson
 Contractor: G. W. Keyes Drilling Co.
 Location: Mueller #2 - ✓
 Commenced: May 25, 1944
 Completed: June 5, 1944
 Potential: 2260 BBLs
 Acid: 500 Gals.

315' of 8 3/4"
 3584' of 5 1/2" Electric Weld

285	Sand - Shale
315	Red Bed
685	Red Bed and shale
1160	Shale & shells
1180	Salt
1510	Salt, shale, shells
1555	Anhydrite
1955	Broken Lime
2165	Lime & shale
2200	Lime broken
2415	Shale
2765	Shale & shells
2860	Lime broken
3200	Lime
3274	Broken Lime
3410	Lime
3470	Lime broken
3495	Lime
3505	Chert
3535	Chert Lime
3585	Shale & lime
3589	Lime
3590	Total Depth

RECEIVED
 STATE CORPORATION COMMISSION

JUL 07 1983

CONSERVATION DIVISION
 Wichita, Kansas