

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 29 Twp. 21S Rge. (E) 12 (W)

Location as "NE/CNW%SW%" or footage from lines C S/2 S/2 NE/4

Lease Owner Morris Sitrin, Inc.

Lease Name Tieperman "B" Well No. 3

Office Address P. O. Box 3467, Tulsa, Okla. 74101

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 19

Application for plugging filed Sept. 16, 1969

Application for plugging approved Sept. 16, 1969

Plugging commenced Sept. 16, 1969

Plugging completed Sept. 16, 1969

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren

Producing formation Depth to top Bottom Total Depth of Well 3605 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	310'	8-5/8"	310'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 450 feet. Set first plug at 450 feet with 50 sacks cement.
Filled hole with heavy mud to 275 feet. Set second plug at 275 feet with 25 sacks cement.
Filled hole with heavy mud to 40 feet. Set third plug at 40 feet with 10 sacks cement.
Bridged rat hole with 2 sacks cement. Job complete at 5:00 AM 9/16/69.

RECEIVED
STATE CORPORATION COMMISSION
SEP 24 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
E. E. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) E. E. Hall

830 Sutton Place - Wichita, Kansas 67202 (Address)

SUBSCRIBED AND SWORN to before me this 22 day of September, 1969

Barbara J. Layton
Barbara J. Layton Notary Public.

Feb. 1, 1972



GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

TIEPERMAN "B" #3
C S/2 S/2 NE/4 Section 29-21S-12W
Stafford County, Kansas

Commenced: September 9, 1969
Completed: September 16, 1969

OPERATOR - Morris Sitrin, Inc.

DEPTH		FORMATION	REMARKS
From	To		
0	200	Sand and shale	
200	310	Red bed	Ran 15 joints 8-5/8" casing, set @ 310' w/225 sacks cement.
310	665	Red bed	
665	690	Anhydrite	
690	1140	Shale and shells	
1140	3040	Shale and lime	
3040	3605	Lime	
3605	TD		Dry and abandoned.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the C-S/2 S/2 NE/4 Section 29-21S-12W, Stafford County, Kansas, to the best of my knowledge and belief.

E. E. Hall

E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 22 day of September, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972.

Barbara J. Layton
Barbara J. Layton, Notary Public

