

TATE OF KANSAS  
TATE CORPORATION COMMISSION  
30 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-02-3-117

API NUMBER 15-185-10505-0000

LEASE NAME Fischer "A"

WELL NUMBER 3

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

4290 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 29 TWP. 21S RGE. 12 (E) or (W)

COUNTY Stafford

LEASE OPERATOR Berenergy Corporation

ADDRESS 3333 S. Wadsworth Blvd. #218 Lakewood, CO. 80227

PHONE # 3031 969-9610 OPERATORS LICENSE NO. 4967

Date Well Completed 1-27-45

Character of Well \_\_\_\_\_

Plugging Commenced 9-12-00

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-14-00

The plugging proposal was approved on \_\_\_\_\_ (date)

by Richard Lacey (KCC District Agent's Name)

Is ACC-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3640'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				10-3/4"	315'	None
				7"	3598'	720'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Set CIBP @3250' and dumped 4 sks. cement on top. Shot pipe @720', ran 2" tubing to 600' and pumped 75 sks. cement and 15 sks. gel, pulled up to 350' and pumped 75 sks. cement, pulled up to 60' and circulated cement to surface. 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

RECEIVED  
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berenergy Corporation SEP 29 2000

STATE OF Kansas COUNTY OF Rice, ss.

CONSERVATION DIVISION  
Wichita, OK

Mike Kelso (Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 28th day of September, 2000

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_

IRENE HERZBERG  
State of Kansas  
My Appl. Exp. Aug. 24, 2001

Form CP  
Revised 05-