

15.185.12632.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Dorby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER Completion 6-27-44

LEASE NAME Teiperman "A"

WELL NUMBER 2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 29 TWP. 21S RGE. 12W (E) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 8-5-93

Plugging Completed 8-10-93

LEASE OPERATOR Energy Three, Inc.

ADDRESS Box 1505, Great Bend, KS 67530

PHONE# (316) 792-5968 OPERATORS LICENSE NO. 5430

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filled? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3607'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	300'	None
				5 1/2"	3597'	1716'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sanded bottom to 3550' & 5 sks cement. Shot @ 2410', 2110', 1810' & 1716'. Pulled pipe. Plugged well w/300# hulls, 10 gel, 50 sks cement, 10 gel, 100# hulls, 125 sks cement. 60/40 pos 6% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Energy Three, Inc.

AUG 19 1993

STATE OF Kansas COUNTY OF Rice, ss.

CONSERVATION DIVISION

R. Darrell Kelso (Employee of Operator) or Wichita, Kansas of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 18th day of August, 19 93

Irene Herzberg
Notary Public

My Commission Expires:

