

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-22-3-117

API NUMBER Drilled 8/26/45

LEASE NAME Tieperman

WELL NUMBER A-5

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

330 Ft. from S Section Line

4620 Ft. from E Section Line
C/SL SW SW

SEC. 29 TWP. 21 SRGE. 12W (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 8-24-88

Plugging Completed 8-30-88

LEASE OPERATOR Lasmo Energy Corporation

P.O. Box 1365

ADDRESS Great Bend, Kansas 67530

PHONE# 310 792-2585 OPERATORS LICENSE NO. 4678

Character of Well Oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? N/A If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3591' Bottom 3593' T.D. 3593

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	284'	none
				5-1/2"	3591'	1798'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Plugged off bottom with sand to 3540' and 5 sacks cement. Shot pipe @2010', 1798', pulled a total of 57 joints of 5-1/2" casing. Plugged surface with 4 hulls, 10 gel, 50 cement, 10 gel, 1 hull, 8-5/8" plug and 125 cement, 60/40 pos, 6% gel.

Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]


Box 347

(Address) Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 2nd day of September, 1988

[Signature]
Notary Public

Commission Expires: _____



RECEIVED
STATE CORPORATION COMMISSION
SEP 13 1988

COPY
CONSERVATION DIVISION
Wichita, Kansas

15.195.12633.0000

Teiperman # 5A CSL SW SW Section 29-21S-12W Stafford County, Kansas

Company : S. A. Murphy
Contractor : Virginia Drilling Co. Inc.
Commenced : July 7, 1945
Completed : August 26, 1945
Total Depth : 3593 Rotary - T.D. 3603
Elevation : 1862

Lasmo

FORMATION	DEPTH
Soil & Sand	0- 230
Red Shale	230- 303
Com. 2S4' - 3 5/8"	
R.R.-Sand-Shale	303- 475
Red Bed, Shale	475- 565
Red Beds	565- 663
Anhydrite	663- 681
Shale-Shells	681-1140
Salt-Shale-Shells	1140-1315
Salt-Shells	1315-1440
Lime	1440-1675
Cherty Lime	1675-1735
Lime Hard	1735-1800
Cherty Lime	1800-1825
Lime	1825-2200
Lime-Shale	2200-2300
Slope test @ 2200' - O.Z.	
Broken Lime	2300-2400
Lime-Shale	2400-2495
Shale-Lime	2495-2625
Lime	2625-2655
Lime-Shale	2655-2745
Lime	2745-2790
Shale-Lime	2790-2840
Lime	2840-2965
Lime Broken	2965-3045
Lime	3045-3195
Slope Test : 3150' - 1' off	
S.L.M. : 3229	
Shale	3195-3260
Lime	3260-3499
Cherty Lime	3499-3525
Lime	3525-3535
Lime-Shale	3535-3565
Shale	3565-3588
Sand	3588-3591
Arbuckle	3591-3593
Arbuckle	3593-3603

Top K.C. 3287
Top Viola 3499
Top Simpson 3537
Top Arbuckle 3591

Circ. 1 1/2 hrs. @ 3580
Circ. 1 3/4 hrs. @ 3585
Circ. 2 hrs. @ 3591

Drilled plug - 700' fill-up in
12 hrs.
2900' total fill-up after 500
gal. acid.

State Potential September 19, 1945
80 barrels

RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1945

CONSERVATION DIVISION
Wichita, Kansas

Now comes S. A. Murphy, who states that he is familiar with the drilling of oil and gas wells and knows of his own knowledge that the Teiperman # 5A located in the CSL SW SW of Section 29-21S-12W Stafford County, Kansas, was drilled to a total depth of 3603 feet. Oil being found in the Siliceous-Lime.

S. A. Murphy

Subscribed and sworn to before me, a Notary Public, this 15th day of October, 1945.

Wm. Lee G. ...
Notary Public

My commission expires: February 5, 1949.