

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

15-185-12584-00-00
API NUMBER 04/27/1943

LEASE NAME Tipperman "B"

WELL NUMBER #1

3300 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 29 TWP. 21S RGE. 12 (E) or (W)

COUNTY Stafford

Date Well Completed 05/18/43

Plugging Commenced 10/15/02

Plugging Completed 10/17/02

RECEIVED
OCT 23 2002

TYPE OR PRINT
NOTICE: Fill out completely
and return to Coas. Div.
office within 30 days.

LEASE OPERATOR Energy Three, Inc.

ADDRESS Box 255, Gorham, KS 67640-0255

PHONE# (785) 637-5321 OPERATORS LICENSE NO. 5430

Character of Well Oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on October 14, 2002, (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? Unknown If not, is well log attached? No

Producing Formation _____ Depth to Top 3394' Bottom 3583' T.O. 3583'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0'	300'	8-5/8"	300.0'	0.00'
	Production	0'	3581'	5-1/2"	3581.5'	1548.45'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Bottom plug. Sand well back to 3300', spot 5sx cement. Pull stretch into pipe & cut off @ 1520'. Pulled to 670', spot 10sx gel w/50sx cement - no circ. Pulled to 320', spot 15 bbl. water - no circ. Spot 21sx gel w/500# hulls - got circ. Spot 50sx cement. Pulled to 40' and circulate 15sx cement to surface. Tore down and moved off.

Name of Plugging Contractor D.S. & W. Well Servicing, Inc. License No. 6901


Address P.O. Box 231, Claflin, KS 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Energy Three, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Edward S. Nennich (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Edward S. Nennich

 KAREN J. MITCHELL
Notary Public - State of Kansas
My Appt. Expires 4/13/06

(Address) P.O. Box 231, Claflin, KS 67525

SUBSCRIBED AND SWORN TO before me this 21st day of October, 2002

Karen J. Mitchell
Notary Public

My Commission Expires: April 13, 2006

OR