

15-185-12335-0001

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Stafford County, Sec. 29 Twp. 21 Rge. 12W (E) (W)

Location as "NE/CNWxSWx" or footage from lines Hxx Ahlgrim #1 C 5/2 NW NE  
Lease Owner Sittrin Petroleum Corporation  
Lease Name H. Ahlgrim #1 Well No. \_\_\_\_\_  
Office Address Great Bend, Kansas 67530  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 5/21/71 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 5/22/71 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4074 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	310	none
				4-1/2"	3952'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 4074', ran sand to 3925', dumped 4 sacks of cement.  
Cut pipe off, set 10' rock bridge at 400' and ran 4 yards concrete.

PLUGGING COMPLETE.


RECEIVED  
STATE CORPORATION COMMISSION  
JUL 19 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
CHASE, KANSAS  
(Address)

Subscribed and sworn to before me this 3rd day of June 19 71  
Margaret Melcher Notary Public.




G. W. KEYES DRIG. CO.  
H. Ahlgrim No. 1.

SEC. 29 T. 21 R. 12 W  
CS $\frac{1}{2}$  NW NE

Total Depth. 3637'  
Comm. 10-5-43 Comp. 10-21-43  
Shot or Treated  
Contractor.  
Issued. 12-18-43

County. Stafford



CASING:  
10 $\frac{3}{8}$ " 310'

Elevation. 1860

Production. Dry

Figures Indicate Bottom of Formations.

soil, sdy shale	35
sand	240
red rock	655
lime anhydrite	665
lime	690
shale & shells	1200
salt, shale, shells	1480
lime & shale	1540
lime	1565
sdv lime	1615
shale & lime	1710
sdv lime	1745
shale & lime	1850
lime brkn	2090
lime & shale	2170
lime brkn	2340
shale	2420
shale & shells	2625
shale & lime	2710
lime brkn	2790
shale & lime	2930
lime & shale brks	2970
lime brkn	3015
lime	3145
lime brkn	3225
shale & shells	3240
shale	3254
lime sh oil	3369
lime	3440
lime & shale	3485
shale	3505
lime	3550
conglomerate	3571
sand	3590
shale, chert, congl.	3637
Total Depth.	

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 3 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Virginia Drilling Co., Inc.  
New Hole

Lime	3859
Lime Cherty	3898
Lime	3919
Lime Cherty	3945
Lime	3998
Lime Cherty	4060
Lime	4074

Granite Wash or  
Arbuckle Limestone 4074 - Total Depth.

174

4 $\frac{1}{2}$ "<sup>OD</sup> Drill pipe casing set at 3952 with 800 sacks cement.  
Cement top to bottom.

Since at 3951'