

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 29 TWP. 21S RGE. 12W E/W
Location as in quarters or footage from lines:
NW SW SE

Lease Owner Southern States Oil Company
Lease Name Mueller #4 Well No. _____
Office Address P.O. Box 1365 Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 11-30-81
Plugging completed 12-7-81
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz
Producing formation _____ Depth to top _____ bottom T.D. 3596'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	280'	none
				5-1/2"	3590'	312'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Shot casing @420' and 317'. Pulled 13 joints of pipe. Tied onto surface pipe and pumped in 2 sacks hulls, 10 sacks gel and 15 sacks cement and got circulation behind surface pipe. Run 300' of tubing, circulated 8-5/8" with 100 sacks cement from 300' to base of cellar. Pulled tubing, swedged 8-5/8" in and pumped 30 sacks cement under pressure. Plugging Completed.

RECEIVED
STATE CORPORATION COMMISSION
DEC 14 1981
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of December, 19 81



Irene Hoover
Notary Public.

My Commission expires: _____

15-185-12627-0000

RECEIVED
STATE CORPORATION COMMISSION

Isern Brothers et al, Owners - Mueller No. 4
NW SW SE Section 29, Township 21S, Range 12 West,
Stafford County, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Elevation 1864

Figures indicate bottom of formation
0 to 215 sand

Tops, corrected 3' to derrick floor

Heebner shale	3112
Base Oread	3142
Brown lime	3244
Lansing	3267
Viola Chert	3496
Simpson Shale	3537
Arbuckle dol.	3587

215	sand
235	shale
285	red bed
655	red bed, shale and shells
685	anhydrite
1160	shale and shells
1250	salt and shells
1540	shale and shells
1645	shale and lime
1975	lime
2075	lime and shale
2245	broken lime
2835	shale and shells
3167	lime
3240	shale and shells
3539	lime
3588	shale
3590	sandy shale
3593	lime
3593	total rotary depth

Casing Record:
8 5/8" set at 280'
5 1/2" set at 3590'

Rotary commenced Jan. 23, 1948
completed Feb. 3, 1948

Cable Tools commenced 2-7-48
completed 2-15-48

CABLE TOOL WORK

Moved in cable tools, bailed hole, drilled cement
and cleaned out to total rotary depth. Drilled deeper.

3596 lime
3596 Total Depth DF

STATE OF KANSAS)
COUNTY OF BARTON) SS

I, G. W. Keyes, Drilling Contractor of the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

Subscribed and Sworn to before me this 4th day of March, 1948.

G. W. Keyes
George A. Meyer
Notary Public

My commission expires Feb. 10, 1951.

CONSERVATION DIVISION
Wichita, Kansas

OCT 8 1991

RECEIVED
STATE CORPORATION COMMISSION