


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Stafford County, Sec. 17 Twp. 21S Rge. (E) 13 (W)

Location as "NE/CNW/SW" or footage from lines NE SW SW  
Lease Owner Circle Oil Company, Inc.  
Lease Name MILLER Well No. 1  
Office Address 816 Bitting Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5/22/65 19\_\_  
Application for plugging filed 19\_\_  
Application for plugging approved 19\_\_  
Plugging commenced 5/22/65 19\_\_  
Plugging completed 5/22/65 19\_\_  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Archie Elving)

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3705 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	313	8-5/8"	5/15/65	
	Surface					
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy Mud from Total Depth to 275 feet;  
Hull Plug and Wooden Plug and 25 sacks  
cement through drill pipe; Heavy Mud to  
40 feet, another plug and 10 sacks Cement;  
2 sacks in Rat Hole.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 25 1965

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sage Drilling Co., Inc.  
Address 816 Bitting Building, Wichita, Kansas.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Lawrence F. Gray (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lawrence F. Gray  
816 Bitting Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of May, 19 65

My commission expires November 26, 1966.  
Louise K. Whitted - Notary Public.

DRILLERS LOGMILLER NO. 1

CASING RECORD:	COMPANY:	Circle Oil Co.	DESCRIPTION:
8-5/8" @ 313' w/150 sacks cement	CONTRACTOR:	Sage Drilling Co.	NE SW SW Sec. 17-21S-13W Stafford Co., Kansas
TOTAL DEPTH: 3705'	COMMENCED:	May 15, 1965	ELEVATION: 1909 KB
	COMPLETED:	May 22, 1965	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Shale	0	313	
Sand, Shale & Shells	313	801	
Anhydrite	801	828	
Shale & Shells	828	1635	
Shale & Sandy Lime	1635	1851	
Lime & Shale	1851	2154	
Shale & Shells	2154	2720	
Lime & Shale	2720	3030	
Sandy Lime & Shale	3030	3165	
Lime & Shale	3165	3393	
Lime	3393	3705	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING COMPANY, INC.

*Lawrence F. Gray*  
Lawrence F. Gray

Subscribed and sworn to before me this 24th day of May, 1965.

*Louise K. Whitted*  
Louise K. Whitted, Notary Public

My Commission expires:  
November 26, 1966.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 25 1965  
CONSERVATION DIVISION  
Wichita, Kansas