

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Stafford SEC. 17 TWP. 21S RGE. 13 XE/W  
Location as in quarters or footage from lines:  
NW NW SW


Lease Owner Kansas Energy Corporation  
Lease Name Fisher Well No. 1  
Office Address 1919 Fourth National Bank Bldg., Tulsa, OK 74119  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed February 25, 1983  
Application for plugging filed February 25, 1983  
Plugging commenced February 25, 1983  
Plugging completed February 25, 1983  
Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3730'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

- 1st Plug @ 3730' w/50 sx.
  - 2nd Plug @ 810' w/50 sx.
  - 3rd Plug @ 360' w/40 sx.
  - 4th Plug @ 40' w/10 sx.
  - 5th Plug @ Rathole w/10 sx.
- Plug down 3:00 PM, February 25, 1983  
Plugged w/165 sx. 50/50 Pozmix, 4% Gel, 3% CC

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing

STATE OF Kansas COUNTY OF Sedgwick, ss.

K.T. Woodman (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, stated and given herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

MAR 8 1983


(Signature) K.T. Woodman  
1008 Douglas Building, Wichita, KS  
(Address)

CONSERVATION DIVISION  
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 7th day of March, 19 83

Kathryn A. Voigt  
Notary Public.

My Commission expires: April 20, 1985 Kathryn A. Voigt



K. T. WOODMAN  
 RES. PHONE 733-0418  
 OFF. PHONE 265-7650  
 WICHITA, KANSAS

D. J. IANNITTI  
 PHONE 792-2921  
 GREAT BEND, KANSAS

**WOODMAN & IANNITTI DRILLING COMPANY**  
*Rotary Drilling Contractors*

1008 DOUGLAS BUILDING  
 104 S. BROADWAY  
 WICHITA, KANSAS 67202

March 7, 1983

Company:	Kansas Energy Corporation
Farm:	Fisher #1
Location:	NW NW SW
Section:	17-21S-13W
County:	Stafford
Contractor:	Woodman & Iannitti Drilling Company
Comm:	February 19, 1983
Comp:	February 25, 1983
Total Depth:	3730'
Casing:	8-5/8" 23# set @ 300' w/275 sx. Common, 3% CC, 2% Gel

Figures Indicate Bottom Formations:

70	Sand
150	Sand
300	Shale
760	Shale & Red Bed
802	Red Bed
829	Anhydrite
1380	Shale
1860	Shale
2220	Shale & Lime
2505	Lime & Shale
2780	Shale & Lime
2965	Lime & Shale
3100	Lime & Shale
3220	Lime
3360	Lime
3410	Lime
3515	Lime
3590	Lime
3700	Lime
3711	Lime
3730	Arbuckle

I certify the above to be a true and correct copy of the Drillers Log to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING COMPANY

*K. T. Woodman*

K. T. Woodman, Partner