

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 17 TWP. 21S RGE. 13W-E/W
Location as in quarters or footage from lines:
C-NE SW

Lease Owner Parrish Corporation
Lease Name Fischer Well No. 1
Office Address 110 N. Market-Suite 201, Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed March 12, 1981
Application for plugging filed Verbal Application
Plugging commenced March 12, 1981
Plugging completed March 12, 1981
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. Leslie

Producing formation _____ Depth to top _____ bottom T.D. 3,687'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	377'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,687 ft. (rotary total depth) to 520 ft. Set plug at 520 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 520 ft. to 270 ft. Set plug at 270 ft. and cemented with 30 sacks cement. Filled hole with heavy rotary mud from 270 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 15 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well Cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
410 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Gary Younger, Agent ~~(employee of owner)~~ ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
251 N. Water Suite 10, Wichita, KS
(Address) 67202

SUBSCRIBED, AND SWORN TO before me this 26th day of March, 19 81

Elsie Willison
Elsie Willison - Notary Public.

My Commission expires: July 25, 1982

MAR 31 1981
CONSERVATION DIVISION
Wichita, Kansas
STATE CORPORATION COMMISSION

KANSAS DRILLERS LOG

COMPANY Parrish Corporation

SEC. 17 T. 21S R. 13W

FARM Fischer NO. 1

LOC. C-NE SW

COUNTY Stafford

ROTARY TOTAL DEPTH 3,687'

COMM. March 6, 1981

COMP. March 12, 1981

CONTRACTOR H-30, INC. (Rig #11)

ISSUED March 26, 1981

CASING

10 3/4"

8 5/8" Set at 376' by Rosencrantz-Bemis

ELEVATION 1,910' K.B.

5 1/2"

4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale	1,535'
Anhydrite	1,657'
Shale	2,305'
Shale and Lime	3,106'
Lime and Shale	3,300'
Shale and Lime	3,425'
Lime	3,675'
Shale	3,687'
Rotary Total Depth	3,687'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Gary Younger
Gary Younger


RECEIVED
STATE OF KANSAS
STATE OF KANSAS

MAR 31 1981

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas)
) ss:
County of Sedgwick)

Subscribed and Sworn to before me a Notary Public in and for said county and state this 26th day of March, 1981.



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:
July 25, 1982