

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15.185.10616.0001

LEASE NAME Grow

WELL NUMBER #2

3300 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 17 TWP. 21 RGE. 13 (E) or (W)

COUNTY Stafford

Date Well Completed 7-16-51

Plugging Commenced 4-21-88

Plugging Completed 9-22-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR John J. Darrah, Jr.

ADDRESS 412 E. Douglas, Suite #1, Wichita, Ks. 67202

PHONE # 316-263-2243 OPERATORS LICENSE NO. 5088

Character of Well Injection

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 8, 1988 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached? With application

Producing Formation Depth to Top Bottom T.D. 3686'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 807' | None |
| | | | | 5-1/2" | 3681' | 682.59' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 2450' and 5 sacks cement. Pulled 23 joints of 5-1/2" casing. Ran 2 1/2" tubing to 741.63' Howco mixed 10 sacks gel and 50 sacks 60/40 pozmix with 2% gel and 3% CC on vacuum. WOC 1 hr. SLM 780' mixed 110 sacks cement blended with 30 # hulls on vacuum. SION. Ran SLM to 1157'. Ran tubing to 1263.75 TD. Mixed 75 sa
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Gt. Bend, Ks. 67530

OVER
RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John J. Darrah, Jr.

STATE OF Kansas COUNTY OF Barton, ss.

OCT 4 1988

James W. Rockhold (Employee of Operator) CONSERVATION DIVISION of
above-described well, being first duly sworn on oath, says: That I have knowledge of Wichita, Kansas facts,
statements, and matters herein contained and the log of the above-described well, as filed that
the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 3rd day of October, 1988

Jona M. Leatherman
Notary Public

My Commission Expires:

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp.

50/50 pozmix with 2% gel, 2% gel, 2% CC, 1/4# floreal per sack, and 200# hulls at 1234', 75 sacks at 720', and 110 sacks with 100# hulls at 320' circulated to surface. Pulled tubing and capped to surface.

